

- ENCLOSURE (UL LISTED) MOUNTED TO WALL.
- 3" CONDUIT AND SWEEP ELL FOR LEAD WIRES. 11
- SATELLITE ASSEMBLY. ASSEMBLED ON BACKBOARD BY SITEONE GREEN TECH.
- 1" CONDUIT AND SWEEP ELL FOR MASTER VALVE WIRES.

TERMINAL STRIP FOR VALVE WIRES.

- 1" CONDUIT AND SWEEP ELL FOR 110 VAC POWER LINE.
- POWER SWITCH / GFCI RECEPTACLE.

- 1" CONDUIT AND SWEEP ELL FOR GROUND WIRE.
- ELECTRICAL FLEX CONDUIT FOR POWER.
- 10" ROUND VALVE BOX AROUND GROUND ROD. FILL WITH 3/4" CRUSHED ROCK.
- COORDINATE ALL CONDUIT RUNS THROUGH FOUNDATION FLOOR BEFORE CONCRETE POUR.
- 5/8" X 8' GROUND ROD WITH #6 GROUND WIRE AND CLAMP. LOCATE 8'-12' FROM ENCLOSURE.

FINISHED GRADE.

#6 GROUND WIRE SECURED TO BACKBOARD GROUNDING TERMINAL.

- 8 FLOW SENSOR TERMINAL BOARD.
- BUILDING WALL. ENSURE WALL AND ANCHORING ARE RATED FOR ENCLOSURE WEIGHT.

NOTE: SEE IRRIGATION LEGEND CALL OUT FOR INCLUDED SATELLITE COMMUNICATION COMPONENTS. SUGGESTED CONDUIT SIZES MAY NEED TO BE LARGER.

SA18 - STRONGBOX: SB-36SSW (36"W x 36"H x 12"D) FRONT ENTRY WALL MOUNT ENCLOSURE

SATELLITE ASSEMBLY (SA)

